

CESSNA 172 PRE-FLIGHT INSPECTION

COMPLETE ALL ITEMS BEFORE ENGINE START. DO NOT SKIP STEPS.

EXTERIOR INSPECTION

FUSELAGE & CONTROL SURFACES

Check for visible damage or loose panels.....

Check

Verify all control surfaces move freely.....

Check

Inspect landing gear for proper extension.....

Check

Check tire pressure and condition Check

Verify pitot tube cover removed Check

END

ENGINE & PROPELLER

Check oil level (6-8 quarts) Check

Inspect propeller for nicks or damage . Check

Check fuel sump for water/contamination.....

Check

Verify fuel caps secure and vented Check

Check engine cowling secure Check

END

COCKPIT PREPARATION

PRE-START CHECKS

Set parking brake Check
Master switch ON Check
Check fuel quantity (both tanks) Check
Verify circuit breakers in Check
Set altimeter to field elevation Check

END

ENGINE START

Mixture RICH Check
Throttle 1/4 inch Check
Master ON, Starter ON Check
Verify oil pressure within 10 seconds . Check
Check ammeter shows charge Check

END

BEFORE TAKEOFF

RUNUP CHECKS

Magnetos check (max 150 RPM drop) . Check
Carb heat check (100-150 RPM drop) . Check
Flight controls free and correct Check
Trim set for takeoff Check
Seatbelts and harnesses secure Check

END